

The Very Best in Comedy and Live Events TECHNICAL SPECIFICATIONS

AUDIO:

Front of House Booth

Midas Pro 2

Klark Technic Network Bridge - Madi Card RME MADIface

There are **44 available mic lines**There are a further 12 mic inputs at FOH.

The desk's output matrix is used for sending 6 outputs to the sound system and there are also 6 aux outputs to stage from FOH.

PA Specification

L'Acoustic DV-Dosc 4 way system plus L'Acoustic front fills and L'Acoustic delays.

Subs: L'Acoustic SB218s (6)

Microphones and DIs

Assorted microphone package - please inquire for specifics.

Monitors

Noise Control SM / ASYM Series 5 x NCA SM 15P Passive 1 x 15" + 1 x 1.4"

Monitor Desk

No in house monitor desk

DJ Equipment

2 x Technics 1210's - No Cartridges or Styli supplied by Venue 2 x CDJ 2000 Nexus Mark 2 1 x Pioneer DJM 750K

LIGHTING:

Lighting Control and Dimming

Avolites Quartz
36 channels Dim-ming + Hot Power

Lighting Fixtures

12 Rogue RH1 hybrids

6 Qwash 419

STAGE:

Depth 4 metres
Width 8 metres
Height to truss 5 metres

Risers

4 x 1metre x 2 metre steel deck 16 x 1' legs 8 x 2' legs

4 meter Fly Bar for Backdrops

Larger Backdrops can be accommodated using other points.

Rigging / Ladders / Barriers etc

Komedia Bath does not have an in house crowd barrier but we do have good links with local hire companies stocking mojo type barrier. Which are installed and insured to current legislative requirements. Any outside hire / install of barrier of any type will require risk assessment, insurance doc-uments and sign off on day of install. Show will not proceed with a barrier that does not comply.

POWER:

1x 125A 3phase into our Avolites Art Rack and have 32A 3 Phase available out of the utility bay. We use this for motor control but are happy to disconnect and use for guest power.

2 x 32A single phase power for audio use on stage 1 is used for our PA and the other is guest line.

10 x Double 13A UK Sockets

1 x 32A Single phase at FOH 8 x Double 13A UK Sockets at FOH

NOISE LEVELS / CURFEW:

Komedia requires all guest engineers, artists and crew to keep to FOH limit of 102 dBa (as measured by the house technician and with the house decibel meter). In general there is a 1700hrs curfew (at the earliest) on the commencement of high sound levels. The after show curfew is dependent on the event, please ask for more information.

ADDITIONAL EQUIPMENT:

We can arrange and hire in a large array of extra equipment as and when required. Payment for this needs to be agreed and arranged with promoter / artist / venue prior to shows and confirmation of equipment hire.